

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: **ENERGIZATION OF SCHOOL DIVISION OFFICE BUILDING**

Brief Description: Supply and delivery of various electrical materials

Location: Brgy. Panubigan, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
1.	22	pcs.	Crossarm, 3" x 4" x 8'	2,900.00		
2.	44	pcs.	Flat Brace 28" long	232.00		
3.	3	pcs.	Double Arming bolt, 5/8" x 16"	144.00		
4.	19	pcs.	Double Arming bolt, 5/8" x 18"	152.00		
5.	9	pcs.	Double Arming bolt, 5/8" x 20"	156.80		
6.	10	pcs.	Thimble eye bolt 5/8" x 10	160.00		
7.	2	pcs.	Single upset bolt, 5/8" x 14"	176.00		
8.	10	pcs.	Machine Bolt, 5/8" x 12"	72.00		
9.	2	pcs.	Machine Bolt, 5/8" x 14"	108.80		
10.	24	pcs.	Clamp Loop #2/0	96.00		
11.	34	pcs.	Steel pin 5/8"	160.00		
12.	10	pcs.	Anchor Rod 5/8" x 7	584.00		
13.	4	pcs.	Anchor log, 4 x 8	800.00		
14.	6	pcs.	Anchor expanding 5/8"	960.00		
15.	158	mtrs.	Guy Wire steel high steel	72.00		
16.	8	pcs.	Pin, pole top, 1" tr., 20" long	288.00		
17.	40	pcs.	Pin Insulator 55-5 porc.	416.00		
18.	144	pcs.	Washer, 2 1/4" x 2 1/4" x 3/16", square, flat	25.60		
19.	11	pcs.	Machine Bolt, 5/8" x 10"	81.60		
20.	126	pcs.	Locknut, MF type, 5/8"	14.40		
21.	34	pcs.	Nut, eye, 5/8", conventional	120.00		
22.	64	pcs.	Insulator, suspension 6"	608.00		
23.	32	pcs.	Clamp, Conductor , deadend, Strain #2/0	520.00		
24.	18	pcs.	Clamp, guy, str., 3 bolt, L.D. 7/16	288.00		
25.	5	pcs.	Ground Rod Clamp 5/8"	35.20		
26.	5	pcs.	Rod, Ground, steel 5/8" x 10'	744.00		
27.	10	pcs.	Round Washer 1/2"	20.80		
28.	3	sets	Fuse Cutout w/ Lightning Arrester 10kv	10,500.00		
29.	6	pcs.	Pole,Steel, 40ft.	46,500.00		
30.	1	pc.	Pole,Steel, 45ft.	51,274.80		
31.	58	pcs.	Carriage Bolt	24.00		

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: **ENERGIZATION OF SCHOOL DIVISION OFFICE BUILDING**
Brief Description: Supply and delivery of various electrical materials
Location: Brgy. Panubigan, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
32.	4	pcs.	Pole Clamp 6" diameter	472.00		
33.	3	pcs.	Connector, Hot line clamp,1/0	480.00		
34.	6	mtrs.	Copper Wire #6	499.20		
35.	90	mtrs.	Connector, compression, YHD 150	56.00		
36.	13	sets	Armor Rod Single Support	640.00		
37.	3	sets	Armor Rod Double Support	720.00		
38.	12	pcs.	Clevis, secondary, swinging	152.00		
39.	1	pc.	Secondary Bracket	152.00		
40.	14	pcs.	Insulator, spool, 1¾"Φ groove	64.00		
41.	2	pcs.	Insulator, spool, 3"Φ groove	112.00		
42.	24	mtrs.	Tie Wire, solid #4	40.00		
43.	70	mtrs.	Grounding wire, 3 strand #4	36.80		
44.	3	pcs.	Thimble Eyunut	160.00		
45.	10	pcs.	Oval Eye bolt, ⅝" x 10"	152.00		
46.	1,500	mtrs.	Conductor, bare, ACSR, # 1/0 - 6/1	94.10		
47.	4	pcs.	Guy Grip ¾"	275.00		
			TOTAL			

Brand Model: _____ Delivery Period: _____ Warranty: _____

After having carefully read & accepted your General Conditions. I/We quote on the item/s price/s noted above.

TOTAL BID PRICE (In Words) _____

BID SECURITY: _____

AMOUNT: _____

Submitted by:

Bidder/Supplier

Date: _____

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: **ENERGIZATION OF SCHOOL DIVISION OFFICE BUILDING**
Brief Description: Supply and delivery of various electrical materials
Location: Brgy. Panubigan, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
-----------	----------	---------------	------------------	-----------	-----------	------------

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: **ENERGIZATION OF SCHOOL DIVISION OFFICE BUILDING**
Brief Description: Supply and delivery of various electrical materials
Location: Brgy. Panubigan, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
-----------	----------	---------------	------------------	-----------	-----------	------------
