

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: **SUPPLY AND DELIVERY OF ONE HUNDRED THIRTY-THREE (133) UNITS PREFABRICATED CONTAINER HOUSE**

Agency: CMO, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
1.	133	units	Prefabricated Container House	180,000.00		
			Specification:			
			Size: 3m (w) x 6m (L) x .87m (h)			
			Frame Color: white: 2.3mm			
			Galvanized profile			
			Wall: 50 mm polystyrene insulation			
			Roof: 40mm glass wool with 0. 45 mm steel cover			
			Ceiling: 0.23mm steel sheet			
			Fllor: 1.16x2.83m Water-resistant, high-strength calcium silicate board			
			Door: High-quality steel door 925240mm 1 pc			
			Window: Plastic steel window 9201200mm 2 pcs			
			Hose/Pipe 4 pcs. Rock wool Fiber cotton: 1 roll Sealant: 7 pcs			
			Electricals:			
			2 lights			
			2 sockets1			
			breaker			
			1 switch			
			14m wire			
			*Site Inspection and verification inspection of the installation site prior to commosioning verification of foundation alignment, structural stability and accessibility.			
			* Assembly and installation Supervision of proper assembly and positioning of container units. Checking of structural connections, welding points, bolts, and anchorage systems.			
			* Electrical System Testing Inspection and testing of electrical wirings, outlets, lighting and fixtures			

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: **SUPPLY AND DELIVERY OF ONE HUNDRED THIRTY-THREE (133) UNITS PREFABRICATED CONTAINER HOUSE**

Agency: CMO, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
			* Verification of compliance with applicable electrical safety standards. Door, Window and Lock Inspection Verification of proper alignment and functionality of doors, windows, locks, hinges and sealing system.			
			* Interior and Exterior Finishing Inspection of wall panels, floorings, ceiling, insulation, roofing and weather proofing works.			
			* Safety and Compliance Check Conduct of safety inspection to ensure compliance with local building, fire safety, and occupational standards.			
			* Operational Testing Functional testing of all installed systems and components under actual operating conditions.			
			* Turnover and Orientation/training for end-users regarding operation, maintenance and safety procedures.			
			* Final Acceptance Support Assistance during final inspection and acceptance by the procuring entity/end user.			
			* 1 year warranty support period Preventive maintenance visit Technical assistant hotline or oncall support Delivery and installation supervision.			
			TOTAL			

Brand Model: _____ Delivery Period: _____ Warranty: _____

After having carefully read & accepted your General Conditions. I/We quote on the item/s price/s noted above.

TOTAL BID PRICE (In Words) _____

BID SECURITY: _____

AMOUNT: _____

Submitted by:

Bidder/Supplier
Date: _____

Republic of the Philippines
City of Canlaon
BIDS AND AWARDS COMMITTEE

Control No.: #1

BID FORM

NAME OF PROJECT: **SUPPLY AND DELIVERY OF ONE HUNDRED THIRTY-THREE (133) UNITS PREFABRICATED
CONTAINER HOUSE**

Agency: CMO, Canlaon City

BILL OF QUANTITIES

Stock No.	Quantity	Unit of Issue	ITEM DESCRIPTION	Unit Cost	Unit Cost	Total Cost
-----------	----------	---------------	------------------	-----------	-----------	------------
